BRUHATH BANGALORE MAHANAGARA PALIKE,
Byataryanapura Division

DRAFT TENDER SCHEDULE

Name of Work: Providing RCC drains at Ashwini Garden and parallel roads in Ward No.10

Tender Notification No. EE/VPP/Tender/ /2010-11, Dated : / / 2010
Tender Form Issued to Sri..... Contractor Reg. No. ..... Class
Issued Vide Receipt No. ..... Dated .....

Sl. No.	Quantity as per Sanctioned	Rate as per Sanctioned Estimate	Description	Unit	ORIGINAL / DUPLICATE RATES	
					Figures	Rs. In Words
1	326.30	42.77	Removing B.S. slab of Drain and stacking. (P No.24 / i 5.32 SR 2010-11)	Sqm		
2	111.24	56.16	KSRRB 300-1 : Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2m meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. (P No.126 / i 19.1 SR 2010-11)	Cum		
3	37.08	146.88	KSRRB M300-53: Construction of embankment with approval material Gravel/Murrum with all lifts and leads,transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) (P No. 133 / i 19.60 SR 2010-11)	Cum		
4	37.08	3495.96	KSRB 4-1.3: Providing and laying in position plain cement concrete mix 1:4:8 using 40mm and down size graded granite metal machine, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specification No.KBS 4.1, 4.2 (P No. 12 / i 4.3 SR 2010-11)	Cum		
5	741.60	199.80	KSRB 4-6.4: Providing and removing centering,shuttering, strutting, propping etc.., and removal of form work for vertical surface such as walls at any thickness,including attached pilasters, buttresses,plinth and string courses cost of all materials,labour complete as per specifications. (P No. 14 / i 4.31 SR 2010-11)	Cum		

Sl. No.	Quantity as per Sanctioned	Rate as per Sanctioned Estimate	Description	Unit	RATES	
					Figures	Rs. In Words
6	74.16	5247.72	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slab, staircase, lintels, retaining walls, walls (any thickness) includingattached pilasters, columns,piers, abutments, pillars,posts,struts, buttresses, string or lacing courses,parapets,coping, bed blocks, anchor blocks plain window cills,fillets etc.., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (P No. 12 / i 4.11 SR 2010-11)	Cum		
7	44.50	5204.52	KSRB 4.9.2 : Providing T.M.T steel reinforcement for RCC work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and westage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P No. 16 Item No.4.46 PWD SR 2010-11)	Qntl		
8	247.20	51.30	Refixing stone slabs of drains and pointing in C.M. (1:3) (P No.24 / i 5.33 SR 2010-11)	Sqm		
9	111.24		Leadfor disposalof debris shall be payable at the following rates	Cum		

Signature of the Contractor

Executive Engineer
Byataryanapura Division
B.B.M.P., Bangalore.

" DTS APPROVED "

ಕಾರ್ಯಪಾಲಕ ಇಂಜಿನಿಯರ್
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ.
ಬೃ.ಬೆ.ಮ.ಪಾ. ಯಲಹಂಕ ವಲಯ
ಸಹಕಾರನಗರ, ಬೆಂಗಳೂರು-92.